Peyton Estates Unit Eight

City of El Paso — City Plan Commission — 4/18/2019 SUSU19-00018 — Major Combination



STAFF CONTACT: Karina Brasgalla, (915) 212-1604, brasgallakx@elpasotexas.gov

PROPERTY OWNER: Texas GLO **REPRESENTATIVE:** H2O-Terra

LOCATION: North of Rojas and East of Peyton; ETJ (Extraterritorial Jurisdiction)

ACREAGE: 70.147
VESTED: Yes
PARK FEES REQUIRED: N/A

EXCEPTION/MODIFICATION 1. A modification to allow a 54' ROW.

REQUEST: 2. A modification to allow a 76' ROW. **RELATED APPLICATIONS:** N/A

PUBLIC INPUT: N/A

STAFF RECOMMENDATION: Approval with condition

SUMMARY OF REQUEST: The applicant proposes to subdivide 70.147 acres of vacant land into 327 residential lots, one park, and two drainage ponds within the City's Extraterritorial Jurisdiction. Access to the subdivision is proposed from Peyton Road. This development is vested and is being reviewed under the former subdivision code

SUMMARY OF DCC RECOMMENDATION: Staff recommends approval of Peyton Estates Unit Eight subject to the following condition:


• Staff recommends that the City Plan Commission require the applicant landscape the rear of all double frontage lots pursuant to Section 19.16.080.D of the former subdivision code.




DESCRIPTION OF ANY EXCEPTIONS, MODIFICATIONS, OR WAIVERS

- The applicant is requesting the following modification requests pursuant to Section 19.04.170 of the former subdivision code:
 - 1. To allow a 54' ROW with 34' of pavement, a 5' landscape parkway and a 5' sidewalk. The applicant is proposing to decrease the pavement by 2' and increase the landscape parkway and sidewalk from 4' to 5', which exceeds the minimum DSC standards of the current code. El Paso Country concurs with the proposed cross-section.





PROPOSED




RESIDENTIAL SUB-COLLECTOR (54' RIGHT-OF-WAY)


SCALE: 1"=10"

2. To allow a 76' ROW with 44' of pavement, a 12' median, a 5' landscape parkway and a 5' sidewalk, which exceeds the minimum DSC standards.

REQUIRED



PROPOSED



RESIDENTIAL SUB-COLLECTOR - EMMAROSE WAY (76' RIGHT-OF-WAY)

SCALE: 1"=10"

Section 19.04.170. A.3 of the former code (Modifications of conditions) provides the criteria the City Plan Commission may use to evaluate a modification request from the DSC standards. The section reads as follows:

Section 19.04.170.A.3

The subdivider has demonstrated an alternative method of development that will improve the aesthetic value of the subdivision while giving equal emphasis to safety, economy, tax yield, maintenance cost, response time, drainage, dedication and improvement of parkland and open space amenities, and vehicular access and pedestrian passage.

RELATION OF PROPOSED APPLICATION TO THE CITY'S COMPREHENSIVE PLAN

CONSISTENCY WITH PLAN EL PASO: Subject property is designated G-4, Suburban.

GOAL 2.2:

The City of El Paso should change its growth pattern away from homogeneous land uses and return to a pattern of compact well-connected mixed-use neighborhoods.

POLICY	DOES IT COMPLY?
2.2.4.a.: Each new neighborhood should have a primary civic space such as a square or green near its physical center.	Yes, the proposed 2.17-acre park will be centralized within Peyton Estates Unit Eight.
2.2.2: The design of new neighborhoods and additions to existing neighborhoods should strive for a mix of housing types	No, the proposed development is composed exclusively of single-family residences.

NEIGHBORHOOD CHARACTER: The subject property is located in the ETJ (Extraterritorial Jurisdiction) and is currently vacant. The subject property is surrounded by vacant land, slated for residential development similar to the development proposed by this plat. The nearest school is Mission Ridge Elementary (0.1 miles). A park is proposed within the proposed subdivision. This property is not located within any Impact Fee Service Area.


COMMENT FROM THE PUBLIC: N/A.

PLAT EXPIRATION:


This application will expire on <u>October 18, 2019</u>. Failure to submit the recording plat in accordance with Section 19.08.100 (Recording plat submission) within the specified date, or within an approved six-month extension period, shall necessitate the total resubmission of the major subdivision application which shall be subject to the subdivision regulations in effect at the time of resubmission.

ATTACHMENTS:

- 1. Aerial map
- 2. Preliminary plat
- 3. Final plat
- 4. Modification request
- 5. Application
- 6. Department Comments









| New COLUMN (1997)

COLUMN | Record | R PEYTON ESTATES In the Company of the BEING A PORTION OF C.D. STEWART SURVEY NO. 311
EL PASO COUNTY, TEXAS
CONTAINING IN ALL 3,055,592,27 SQ.FT, OR 70,147
ACRES OF LAND MORE OR LESS A ACCORDANCE WITH TEXAS LOCAL CONSENSURIT CODE 232.023(6), IT IS HEREST EXPRESSED THAT ALL PARCELS CONTRACTS USED BY THE SESSED THAT ALL PARCELS CONTRACTS USED BY THE SESSED WILL CONTRACT A STATEMENT DESCRIBED BY MERY WATTH, SERFE, ELECTROTY, AND GAS EXPRESS BY LEG WATTH, AND LOCAL WAY A STATEMENT DESCRIBED BY MERY WATTH, SERFE, ELECTROTY, AND GAS EXPRESS LECTROTY, AND GAS EXPRESS LECTROTY, AND UOT 33, 8202X 51, AND 10T 13, 8502X 63 ARE DESIGNATED AS PROMOVE AREAS AND RETRIEVE PONDS, NO DRELLAND/OCCUPANCY SHALL BE FROMETTED ON LOTS, NEEDS LOTS SHALL BE SEE DELUCED TO AND MANUARID BY THE PASSED ONL ESTE MANUADRA, UTILITY DISTRICT? BULDE SMLL COCCINCT CONCRET DIVENNS BETHELY THE HOLD CLAB AND THE PROPERTY THE CASI-DEPT AND CONCRETON OF MENDALISTS. THE CASI-DEPT AND COLOR AND ADDRESS OF A PROPERTY THE CONCRETON OF ANY CHEET AND CASE REPLACED OF UNITES CONSTRUCTION OF CONCRETOR OF ANY CHEET AND CASE REPLACED OF UNITES CONSTRUCTION THE CONCRETOR OF ANY CHEET AND CASE. WHICLLAR ACCESS TO LOTS ABUTTING PETTAN HOAD, SHALL BE FROM OTHER GEDICATED STREETS ONLY, THE INSTRUMENT ASSUMEN BELLAR OF ACCESS IS FILED IN THE CL PASO COMENT CLERK OFFICE,
ROWLED ACCESS TO LOTS.
ROWLED A HAIT PETTON ESSATS LLC. THE OWNER AND SUBDINGER OF PETTON ESSATES UNIT DON'T MAINTENEN STATE DE COMMITTENEN DE STOTHE PROPERTY LINES UNLESS OTHERWISE APPROPER IN METTON, BY THE COUNTY DIVINESS. THE PROPERTY LES IN YORK X, AS DESCANTED BY FEMAL COUNTY OF DEADS, COMMONT AND THE AND COMMONT AND THE △ THIS SYMBOL REPRESENTS ALL PROPOSED STREET MONUMENT LOCATIONS.
PROPERTY CORNERS WILL BE SET UPON COMPLETION OF CONSTRUCTION OF ROMOWAYS AND UTILITIES. LICRY SMALL CONSTRUCT A 5 (FMF) FOOT MICE CONCRETE SDEMALK AS PART OF THE MSTRUCTION OF MAPPICIENTS. THE SDEMALKS ARE LOCATED, ALONG FRONT, REAR AND SDES EACH LOT MARKE THE LOT ABUTS A PUBLIC ROAD, PETTON ROAD SMALL BE CONSTRUCTED THE DIVIDLOPIN. MOSC THAN ONE SWALE-FAMILY DETACHED DWILLING SHALL BE LOCATED ON EA LEXTENOR BOWHDARY CORNERS UNLESS OTHERWES NOTED. I 1/2" REBAR WITH YELLOW PLASTIC CAP STAMPED TX 5572, UNLESS OTHERWES UNIT EIGHT FOR PEYTON ESTATES UNIT BOHT ARE FILED IN THE BL PASO COUNTY SURVEY NO. 318, ARED: MARCH 4, 2019 SHEET 2 OF 2



CIVIL ENGINEERING PLANNING LAND DEVELOPMENT SURVEYING WATER

2020 E. Mills Ava. | El Paso, TX 79901 | P (915) 533-1418 | F (915) 533-4972 | H2O-Terra com

February 20, 2019

City 3

801 Texas Ave.

El Paso, Texas 79901

Re: Peyton Estates Unit Eight Combination Plat: 5-Day Review ETJ Modifications (Code # 19.04.170, A3, Alternative Subdivision Improvement Design)

We are respectfully requesting the following modifications:

- A modification for the standard 52-foot-wide right-of-way residential collector to allow for a 5-foot-wide sidewalk, 5-foot-wide parkway, and 34 feet of pavement all within the 54-foot-wide public rights-of-ways within the subdivision. (See Sections on Sheet 2 of Plat)
- A modification for the standard 52-foot-wide right-of-way residential collector (Emmarose Way) to a 76-foot-wide public right of way to allow for a 12.0-foot median, and 44 feet of pavement. (See Sections on Sheet 2 of Plat)

We appreciate your assistance, if you should have any questions please do not hesitate to call.

Sincerely,

Isaac Rodriguez Project Manager







MAJOR COMBINATION APPLICATION

		FILE NO. SUS			
SUBDIVISION NAM	E: Peyton Estates Unit 8	-			
Legal description for the A portion of C.D. S	he area included on this plat (1 Stewart Survey No. 318, El	ract, Block, Grant, etc.) Paso County, Texas			
B					
Property Land Uses:	ACRES SITES		ACRES SITES		
Single-family	43.797 327	Office	ACRES SITES		
Duplex		Street & Alley	21.148 18		
Apartment		Ponding & Drainage	3.031 2		
Mobile Home		Institutional			
P.U.D.	1125 PA NO. 1125	Other (specify below)			
Park	2.171 1				
School					
Commercial		Total No. Sites	348		
Industrial		Total (Gross) Acreage_	70.147		
What is existing zoning of the above described property? N/A Proposed zoning? N/A					
Will the residential site	es, as proposed, permit develop	ment in full compliance with all ze	oning requirements of the		
existing residential zor	ne(s)? Yes	No			
What type of utility easements are proposed: Underground Overhead Combination of Both X .					
What type of drainage is proposed? (If applicable, list more than one)					
Storm run off will be conveyed by surface flow to a series of drainage structures and discharge					
retention ponds through storm pipe. Design standards will meet capacity for a 100-yr storm event.					
		tion with development? Yes			
rue special public imp	toveniens proposed in connec	tion with development: Tes	NO A		
		ubdivision Ordinance proposed?			
If answer is "Yes", please explain the nature of the modification or exception Residential subcollectors shall I wide. TIA waiver, Major arterials exist at Peyton Drive and Rojas Drive. Connectivity index is also explain the nature of the modification or exception Residential subcollectors shall I					
wide. TIA waiver, M	lajor arterials exist at Peytor	n Drive and Rojas Drive. Conne	ctivity index is also ex		
Remarks and/or explar	nation of special circumstances	A variance for the proposed su	bdivision was annrow		
	ers on Oct. 15, 2018	Transmitted that the proposed do	outrision was approve		
Improvement Plans	submitted? Yes_2	C No			
Will the managed auto-	thatalan menterakan tan				
Will the proposed subdivision require the city to review and decide whether this application is subject to the star in effect prior to the effective date of the current applicable standards? Yes X No No					
	wested rights patition in accord	dance with Title I (General Provisio	ne) Chapter 1 (b) - Verse		
If yes, please submit a	vested rights petition in accord	idirec with title I (denetal I lovisto	ita) Chapter 1.04 - veste		

Planning & Inspections Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890 | (915) 212-0085

12.	Owner of record Texas GL	D 1700 N. Congress Dr Austin	TX 78701	800-998-4456
	(Name & A	address)	(Zip)	(Phone)
13.	Developer Hunt Peyton Est	ates LLC 4401 N. Mesa El Pas	o, TX 79902	915-545-2331
(Name & Address)		(Zip)	(Phone)	
14.	Engineer H2O Terra	2020 E. Mills El Paso, TX	79901	915-533-1418
	(Name & A	address)	(Zip)	(Phone)
	ER SIGNATURE	1		
REPRI	ESENTATIVE CONTACT (PHONE):	915-533-1418		
REPRE	SENTATIVE CONTACT (E-MAIL):	_irodriguez@h2o-terra.com		

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS.

Planning & Inspections Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890| (915) 212-0085

PLANNING AND INSPECTION DEPARTMENT - PLANNING:

Developer/Engineer shall address the following comments:

- 1. Per 911, change the name of Eastleigh Drive
- 2. Per CAD, correct the labels for Lots 10 and 11, Block 57
- 3. In CPC approval block, the signature line should read "Planning & Inspections Director"
- 4. Submit to the Planning & Inspections Department Planning Division the following prior to recording of the subdivision.
 - a. Current certified tax certificate(s)
 - b. Current proof of ownership
 - c. Release of access document, if applicable
- 5. Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.

PLANNING AND INSPECTIONS - LAND DEVELOPMENT:

We have reviewed subject plats and recommend Approval.

The Developer/Engineer shall address the following comments:

- 1. The Pond on lot 31 shows a pipe going through a residence into the pond; indicate if it is through a drainage easement or drainage right-of-way.
- 2. At the improvement plan stage, provide protection to the subdivision from all offsite stormwater runoff that may have an adverse impact on any improvements.
- 3. Provide printout of the mathematical closure of the exterior boundary of the subdivision indicating the error of closure.
- 4. At the improvement plan stage, protect the subject property from storm-water runoff from the adjacent terrain and vice versa.
- 5. Remove pond contours and maintenance ramp lines, etc. on final plat sheets.
- 6. At time of construction, Sidewalks must be continuous across alleys with expansion joint separations between asphalt, apron, and sidewalk as per (DSC 6-17).

<u>911:</u>

The District recommends a different street name for Eastleigh Dr. We are concerned that it sounds too close to Eastlake Dr.

CENTRAL APPRAISAL DISTRICT:

Correct lots on Block 57.

EL PASO COUNTY:

The County Planning & Development Department has reviewed the Peyton Estates Unit Eight Subdivision Plat, received on March 11, 2019, and offer the following comments and recommendations:

<u>Preliminary Plat (Sheet 1)</u>

- 1. Change any block and lot numbers as marked in the plat.
- 2. Label all drainage easements.
- 3. Correct the number of residential lots proposed.
- 4. Revise the Owner's Dedication, Certification as shown on plat.

Preliminary Plat (Sheet 2)

1. Label all drainage easements.

- 2. Show the direction of flow on Alley A and B.
- 3. Identify whether there is a proposed high point at the intersection of Eastleigh Drive and Emmarose Way.
- 4. Verify that Paseo Del Este MUD No. 1 will service water and sewer and District No. 7 will maintain the agreed easements and drainage infrastructures.

Engineering Report

- 1. Include the following statement as part of the drainage report section:
 - a. "Improvement plans for this subdivision are referenced in Case ID#XX-XXX at the El Paso County Public Works Department"
 - b. Reference the Case ID # for the subdivisions mentioned.
 - i. The Estates at Emerald Park Unit Two No Case ID, use subdivision name.
 - 1. "Improvement plans for The Estates at Emerald Park Unit Two subdivision are referenced at the El Paso County Public Works Department."
 - ii. The Estates at Emerald Park Unit Four Case ID#10-018
 - 1. "The Estates at Emerald Park Unit Four subdivision improvement plans are referenced in Case ID#10-018 at the El Paso County Public Works Department"
 - c. Identify where flow from drainage area 14 is conveyed.
- 2. Correct the lot numbers on all Water and Waste Water reports.

CAPITAL IMPROVEMENTS DEPARTMENT - Parks:

We have reviewed <u>Peyton Estates Unit Eight</u> a major combination plat map and on behalf of CID Parks & Planning Division, we offer Applicant / Engineer the following comments:

Please note that this is a Residential subdivision composed of <u>327</u> residential lots and includes a <u>2.17-Acre Park</u>; Per City Standards a total of 3.27 acres of "Parkland" would have been required however...

This subdivision is located with-in the City of El Paso Extra Territorial Jurisdiction (ETJ) area but not with-in the areas of potential annexation by the City, therefore meeting the requirements to be excluded from the calculation for "Parkland / fees" as IT IS NOT identified on the official map as described per ordinance Title 19 – Subdivision & Development Plats, Chapter 19.20 - Parks & Open Space as noted below:

Section 19.20.020 - Dedication Required

Dedication Required. All subdivisions located within the corporate limits of the City of El Paso and within those areas designated in the City's extra territorial jurisdiction (ETJ), as identified on an official map kept in the Development Services Department.

TXDOT:

Development is not abutting TxDOT Right of Way.

EPCWID:

Proposed development is outside of EPCWID's district boundary.

SUN METRO:

No objections.

FIRE:

Recommend approval.